

# Limska Draga viaduct: fabrication and erection of orthotropic plates

Autor(en): **Androic, Boris / Dujmovic, Darko / Dumbovic, Ivan**

Objekttyp: **Article**

Zeitschrift: **IABSE reports = Rapports AIPC = IVBH Berichte**

Band (Jahr): **64 (1991)**

PDF erstellt am: **15.08.2024**

Persistenter Link: <https://doi.org/10.5169/seals-49296>

## **Nutzungsbedingungen**

Die ETH-Bibliothek ist Anbieterin der digitalisierten Zeitschriften. Sie besitzt keine Urheberrechte an den Inhalten der Zeitschriften. Die Rechte liegen in der Regel bei den Herausgebern.

Die auf der Plattform e-periodica veröffentlichten Dokumente stehen für nicht-kommerzielle Zwecke in Lehre und Forschung sowie für die private Nutzung frei zur Verfügung. Einzelne Dateien oder Ausdrucke aus diesem Angebot können zusammen mit diesen Nutzungsbedingungen und den korrekten Herkunftsbezeichnungen weitergegeben werden.

Das Veröffentlichen von Bildern in Print- und Online-Publikationen ist nur mit vorheriger Genehmigung der Rechteinhaber erlaubt. Die systematische Speicherung von Teilen des elektronischen Angebots auf anderen Servern bedarf ebenfalls des schriftlichen Einverständnisses der Rechteinhaber.

## **Haftungsausschluss**

Alle Angaben erfolgen ohne Gewähr für Vollständigkeit oder Richtigkeit. Es wird keine Haftung übernommen für Schäden durch die Verwendung von Informationen aus diesem Online-Angebot oder durch das Fehlen von Informationen. Dies gilt auch für Inhalte Dritter, die über dieses Angebot zugänglich sind.



## Limska Draga Viaduct – Fabrication and Erection of Orthotropic Plates

Viaduc Limska Draga – Fabrication et montage de la dalle orthotrope

Limska-Draga-Talbrücke – Werkstattfertigung und Montage von orthotropen Platten

**Boris ANDROIC**

Dr. Eng.  
Univ. of Zagreb  
Zagreb, Yugoslavia

**Darko DUJMOVIC**


Civil Eng.  
Univ. of Zagreb  
Zagreb, Yugoslavia

**Ivan DUMBOVIC**

Consulting Eng.  
IPZ  
Zagreb, Yugoslavia

### 1. INTRODUCTION AND DESCRIPTION OF THE VIADUCT


The preliminary design of the Limska Draga Viaduct was made in 9 solutions. The solution chosen was the steel structure with box cross-section (Fig.1). The choice was dictated by the topography and geology of the site as well as the current economic situation. The relation between the design, fabrication, erection and quality assurance is shown on the orthotropic plate.



**Fig.1** Longitudinal and cross-section

### 2. FABRICATION

The viaduct consists of 45 assemblies consisting of 8 parts each (Fig.2).



**Fig.2** Assemblies

**Fig.3** Computer made shop designs

Workshop designs were made by means of computer in three months and include over 2500 tons steel. The material was chosen in accordance with calculations and criteria against brittle fracture.

### 3. ERECTION

Erection of the assemblies was designed in a way to minimize residual stresses in the orthotropic plate welds. Temporary connection was done by conical bolts over the box ribs. This is done by means of a temporary device which carries the new assembly, which can thus be moved horizontally. The conical bolts along the

upper chord were removed and the assembly was moved 3 mm. After welding the upper ortho plate, the same procedure is repeated for the lower ortho plate.


#### 4. QUALITY ASSURANCE

Geometrical deviations are measured during fabrication and erection. Figs.4a and 4b show deviations of longitudinal stiffeners and transversal beams in the upper orthotropic plate for assembly No 38 during pre-erection.




**Fig.4** Deviations of transversal beams and longitudinal stiffeners

Quality assurance was done in all stages of construction for welding in installation of high strength bolts, etc. Special attention was paid to non-destructive determination of mechanical properties of welded joints by measuring their hardness. Fig.5 and 6 present the results of hardness of shop and site welds.



**Fig.5** Shop weld




**Fig.6** Site welds

The arrangement of hardness intensities are important for the assessment of the welds mechanical properties.

#### 5. FATIGUE ASSESSMENT

Fatigue in an orthotropic plate is analyzed by estimation of traffic, by selecting details of higher fatigue strength and by assessing the location of longitudinal rib splice. Average daily passage of equivalent vehicles is  $n=1200$ .



**Fig.7** Fatigue assessment

#### 6. CONCLUSION

Bearing in mind the interdependence of design, fabrication and erection of the presented orthotropic plate, together with adequate quality assurance, an effective interaction of design and construction technology has been achieved.